



Guadalupe County Fire Marshal Office

Patrick Pinder, Fire Marshal

101 E. Court Street, Suite 208

Seguin, Texas 78155

(830) 303-8856



Fixed Pipe Suppression Systems Plan Submittal Requirements

Fixed Pipe Suppression Systems installed in Guadalupe County shall meet all the requirements of the 2006 International Fire Code, local amendments, as well as all applicable NFPA Standards. All final systems testing and inspections will be witnessed by the Guadalupe County Fire Marshal's Office.

The following is check list of information that should be used as an aid and is not intended to cover every code requirement.

Permit Application

Copy of License current issued by The State of Texas Fire Marshal (1 Copy)

- System Designer
- Contractor/Company
- Installers

Submittal Packet (1 Copy)

- System Design Description
- Manufacturer's Product Information Sheets of Listed Devices
- Flow rates of nozzles
- Specifications for piping
- List of materials
- Addressable Device List/Zone Legend

1/8" Scaled Plans 1 Paper Copy delivered to Fire Marshal's office and 1 PDF

- Legend
- North Arrow
- Plans shall reflect the entire building/suite as well as the area of operation
- All Rooms Labeled for intended
- Arrangement of appliances
- Layout of Piping
- Nozzle arrangement
- Location of Pull Station
- Gas Shut Off and/or Shunt Trip
- All exits and means of egress
- System Designers Stamp with Wet Signature

Required Inspections

- Pull Stations
- Air Test
- Fusible Link
- Gas Shut Off
- Electric Shunt Trip
- Alarm System activation



Guadalupe County Fire Marshal Office

Patrick Pinder, Fire Marshal

101 E. Court Street, Suite 208

Seguin, Texas 78155

(830) 303-8856



Plans review process may take up to 10 working days. Incomplete plans may require that the plans be resubmitted. System acceptance inspections are required and should be called in at least 24 hours prior to requested inspection times. A re-inspection fee of \$50.00 will be assessed on systems that are not in complete compliance with all applicable codes. All devices will be tested in an approved manner.

INSTALLATION/MODIFICATION PERMIT AND AN APPROVED SET OF PLAN SHALL REMAIN AT THE JOB SITE AND PROVIDED TO INSPECTORS WHEN REQUESTED.